

TUMKUR DIVISION.

Notification, dated 3rd March 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 3 P.M., of 3rd April 1933, for constructing an Urdu Girl's School at Kunigal. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1933.

2. The plans, detailed estimates and conditions may be seen at the Executive Engineer's Office, at Tumkur between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 175 in cash or currency notes as earnest money, and be superscribed "Tender for constructing an Urdu Girl's School at Kunigal in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered, cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements, quality of works, etc., and in all disputes of any kind the decision of the Executive Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump sum provisions are subject to modification as per data worked out during the execution. For individual items of work under lumpsum provision the rates tendered for similar items of work will be paid and for other items the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract estimate for constructing an Urdu Girl's School Building at Kunigal.

Sl. No.	Items of work	Unit	Quantity	Rate in figures	Rate in words
				Rs.	Rs.
1	Earthwork excavating foundation and filling in basement.	C.yd.	47		
2	Stone jelly concrete in chunam mortar for foundation.	C.ft.	465		
3	Size stone in clay for foundation and basement including bond stones at 6' apart.	"	1,304		
4	Burnt brick in clay for superstructure	"	1,590		
5	Burnt brick in mortar	"	261		
6	Burnt stone slabs 6" thick roughly dressed and fixed.	S.ft.	420		
7	Teak wood wrought and put up including wood oiling complete.	C.ft.	92.40		
8	Roofing with 1st class Mangalore tiles on teak reapers and wood oiling to reapers complete.	Sqr.	12.62		
9	Ridge tiles set in mortar and painted with cement.	R.ft.	79		

Sl. No.	Items of work	Unit	Quantity	Rate in figures	Rate in words
				Rs.	Rs.
10	Teak wood battened doors with iron clamps and fittings, etc., complete.	S. ft.	39		
11	Teak wood windows with $\frac{1}{2}$ panelled and $\frac{1}{2}$ glazed or expanded metal and $\frac{3}{4}$ " round iron bars clamps, fittings, etc., complete.	"	81		
12	Teak wood trellies work with fittings complete ...	"	9		
13	Perforated brickwork including chunam and plastering complete.	"	41		
14	Flooring with burnt stone slabs 3" x 4" thick roughly dressed the joints and fixed on sand.	Sqr.	6.26		
15	Chunam plastering	"	36.95		
16	Whitewashing 2 coats	"	36.95		
17	Silicate painting 2 coats	"	2.49		
18	Chunam borders over gables roof 9" x 9" and plastering complete.	R.ft.	72		
19	Chunam painting to basement and cement washing.	Sqr.	3.00		
20	Zinc sheets for valleys 3" wide over the teak wood planks 3' wide and $\frac{1}{2}$ " thick including wood oiling and putting valley bunds in mortar and cement plastering complete.	R.ft.	56		
21	Teak wood cave boored plain 9" x 1" including chocolate painting and fixing complete.	"	178		
22	Clearing site and levelling ground and filling in basement if necessary.	Lump sum			
23	Sundry and unforeseen works such as showing false windows at rear of end of rooms, putting black wall boards in cement mortar if necessary and providing glass tiles on roof.	Lump sum			
24	Pergola or pendal Burnt stone pillars 6" thick roughly dressed and fixed including cutting groves on top for pendal in front of the building.	S.ft.	150		
25	Putting Longitudinal and cross bamboos including nails, ropes and thatties or mats for covering, etc.	Lump sum			

N. G. KRISHNA IYENGAR,
Executive Engineer.